PE

PROFESSIONAL ENGINEERING CONTINUING EDUCATION

Transportation Plans & Specifications

Construction Coordination & Nonconforming Work

Self-Paced Course Study Guide



Utility work in transportation corridors. Source: FHWA SHRP2 Kentucky case study, p. 1; source credits District DOT, FHWA and FEMA. These photographs do not document the illustrative UC-17 example.

COURSE	CREDIT / CATEGORY	INSTRUCTOR
ENG-006	4 CEH / PDH · Area of Practice Civil: Transportation	James Barber, P.E.

Superior Learning, LLC d/b/a BuilderCE

Audience: Professional engineers involved in roadway or transportation design, multidisciplinary design coordination, plans and specifications, construction-phase engineering support, project management, quality assurance, field coordination or assessment of constructed work.

TRANSPORTATION PLANS, SPECIFICATIONS & CONSTRUCTION COORDINATION

4 CEH

AOP

CIVIL

Course overview

Course purpose

Transportation projects are built from a coordinated body of information rather than from a single drawing set. Plans communicate geometry and design intent. Specifications establish materials, workmanship, testing, measurement, acceptance, and administrative requirements. Standard plans and details supply repeatable requirements. Approved submittals, requests for information, change documents, testing records, inspection reports, field measurements, photographs, and closeout records then document how those requirements are interpreted and executed during construction.

This course develops a disciplined engineering approach to that information flow. The emphasis is not on memorizing one agency's procedures. It is on learning how a professional engineer identifies the controlling requirement, recognizes conflicts among transportation disciplines, distinguishes field observation from engineering judgment, evaluates deviations, chooses an appropriate disposition pathway, and preserves an auditable technical record. Florida Department of Transportation examples are used because the course is transportation-focused and because FDOT publishes an integrated system of design manuals, standard plans, and standard specifications. The same reasoning applies to other owners when their governing contract documents are substituted.

The course is organized around a recurring question: What is the requirement, what has actually occurred, who has authority to decide, and what evidence closes the issue? That question provides a practical bridge between plans production, construction coordination, inspection, testing, nonconformance management, and project closeout.

Learning objectives

- Explain the respective roles of transportation plans, specifications, standard plans, approved submittals, RFIs, change documents, testing/inspection records, and field information in defining and documenting project requirements.
- Identify common multidisciplinary transportation-plan coordination problems, omissions, ambiguities, and interface conflicts and determine when clarification, interdisciplinary review, or controlled design change is required.
- Use observations, inspection reports, testing results, photographs, measurements, and other construction-phase information while distinguishing reported facts from engineering conclusions, certifications, or acceptance decisions.
- Recognize, document, and classify nonconforming work and describe appropriate corrective, evaluative, acceptance, and escalation pathways.
- Explain how testing results, inspection reports, RFIs, deficiency documentation, photographs, correspondence, change records, and closeout information contribute to an auditable transportation-project record.
- Evaluate applied transportation-project scenarios involving cross-discipline conflicts, field deviations, failed tests, proposed substitutions, design changes, incomplete work, and corrective actions.

Study plan and navigation

MODULE	MINUTES	FOCUS
1	35	Transportation Contract Documents and the Basis for Conformance
2	40	Multidisciplinary Plans, Specifications, Submittals & Coordination
3	45	Construction-Phase Information, Field Coordination & Documentation
4	45	Nonconforming Work and Corrective-Action Pathways
5	40	Testing, Quality Records, Change Documentation & Project Closeout
6	35	Applied Transportation Project Scenarios & Professional Judgment

The 240-minute allocation is an instructional plan, exclusive of the final examination. Individual study time may vary.

How to complete this course

Read all modules in this course and study its diagrams, examples and case explanations. No separate module acknowledgement is required. When you have finished reading, select Continue at the bottom of the BuilderCE lesson page to begin the 10-question final examination. If you are reading the PDF, return to that webpage first. A score of at least 70% is required to pass. Retakes are permitted.

Documented utility record · Worked coordination case · Source links

MODULE 1 | 35 MINUTES

Transportation Contract Documents and the Basis for Conformance

Transportation construction begins long before the first lane closure or excavation. It begins when design requirements are converted into a coordinated set of contract documents that can be priced, built, inspected, measured, and accepted. The field team inherits those documents as an operating system. If the system is internally consistent and the current revision is used, many questions can be answered directly. If it is incomplete, ambiguous, or internally inconsistent, the project needs a disciplined clarification process before the ambiguity is converted into physical work.

This module establishes the baseline for the rest of the course: conformance can be evaluated only after the controlling requirement is identified. A field condition cannot be called conforming or nonconforming in the abstract. It must be compared with the applicable plan, specification, standard plan, approved submittal, revision, or authorized change that governs the work.

1.1 The contract-document system

DOCUMENT	ROLE IN THE REQUIREMENT SYSTEM
Plans / profiles / schedules	Geometry, location, elevations and identified work
Specifications / standard plans	Materials, workmanship, acceptance and referenced details
Project provisions	Contract-specific additions or modifications
Approved submittals	Construction-specific information within the accepted scope
RFIs / field records	Clarification and evidence; authority remains role-specific
Authorized changes	Controlled modification of applicable requirements

Transportation contract documents are complementary. The plan set may establish stationing, geometry, profile, drainage structures, utility interfaces, signing, signalization, pavement markings, quantities, and design-specific notes. Specifications may establish materials, fabrication, construction tolerances, testing, workmanship, measurement, and payment requirements. Standard plans and standard details provide repeatable requirements that need not be redrawn for every project. Special provisions or project-specific technical specifications modify or supplement the standard requirements. Addenda revise the bidding documents. Change orders, supplemental agreements, plan revisions, field directives, or other authorized change instruments modify the construction-stage requirements after award.

A disciplined engineer avoids treating any one document as self-sufficient when the contract requires coordinated use. A drainage structure shown at a station and offset on the plans may also be governed by a standard detail, a pipe material specification, a bedding specification, a testing requirement, a utility clearance, and a pay-item description. The plan gives the location and arrangement; the specification may define what constitutes acceptable material and workmanship. If the two appear inconsistent, the project needs the contract's established order-of-precedence or clarification process rather than an informal choice by whichever person is closest to the work.

The first practical habit is therefore to identify the document family associated with a field question. For a signal pole foundation, for example, the family may include the signal plan, pole schedule, geotechnical assumptions, standard plans, structural details, grounding requirements, utility information, shop drawings, and any approved substitution. For a roadway profile issue, it may include roadway plan/profile sheets, cross sections, drainage information, typical sections, curb-return details, and utility or driveway tie-in requirements.

1.2 Current approved documents are the baseline

A technically correct requirement can still produce a failure if the field is using the wrong revision. Transportation projects accumulate revisions quickly: design changes, utility relocations, permit conditions, addenda, approved value-engineering changes, shop-drawing updates, contractor proposals, agency comments, and responses to RFIs. A printed sheet in a truck may look authoritative while being superseded.

Revision control is therefore part of engineering quality. Before using a document to make a technical decision, verify that it is the current approved version for the decision being made. This applies not only to drawings but also to shop drawings, product data, calculations, temporary traffic-control details, material approvals, testing procedures, and agency criteria that the contract incorporates by reference.

A useful field check is to ask:

- What document is being relied upon?
- What revision, issue date, or approval status applies?
- Has a later RFI response, change document, or approved submittal modified it?
- Is the copy being used in the field the same document available to the reviewer?
- Has the affected discipline been informed of the change?

These questions can prevent a common class of errors in which every individual action is reasonable but the team is acting on different versions of the project.

Practice point - the latest document is not always the controlling document

"Latest" and "applicable" are not always identical. A later drawing may address only one portion of the work. A submittal revision may not be approved. A proposal may be under review. A construction bulletin may apply only to work not yet installed. The controlling requirement is the one that has been validly issued for the work in question under the project's document-control process.

1.3 Plans communicate design intent through coordinated views



Field coordination begins by reading transportation plan information as a coordinated system rather than as isolated sheets. Contextual illustration, not a documented project record.

Transportation plans are often multidimensional even when printed on two-dimensional sheets. Horizontal geometry appears in plan view. Elevations appear in profiles, cross sections, details, drainage structures, utility profiles, or spot elevations. Material and construction requirements may appear in notes or specifications. Typical sections communicate repeated cross-sectional requirements. Standard plans supply details referenced by index. Quantity tables and schedules communicate counts, lengths, sizes, or other information that may also appear elsewhere.

A reviewer should resist reading one sheet in isolation when the issue crosses views. A curb inlet may appear properly located in plan view but be incompatible with the gutter profile. A proposed utility may clear pavement vertically but conflict with a drainage structure laterally. A sign support may meet its plan

location but violate a minimum offset, sight-distance, or clear-zone criterion. A driveway profile may satisfy roadway geometry but create an inaccessible sidewalk cross slope. Coordination requires following the physical system across the sheets that describe it.

One effective technique is the three-view check:

1. Plan - where is the feature horizontally? 2. Profile/elevation - where is it vertically and how does it drain or connect? 3. Section/detail - what is its physical configuration, material, clearance, and relationship to adjacent work?

The technique is simple, but it catches many field conflicts before installation.

1.4 Specifications define more than material names

A specification is not merely a list of acceptable products. Transportation specifications often define required methods, material properties, quality-control activities, testing, tolerances, submittals, sampling frequencies, acceptance criteria, measurement rules, and corrective obligations. FDOT describes its Standard Specifications for Road and Bridge Construction as requirements relating to the manner of performing work and to the quantities and qualities of materials and labor for FDOT contracts. That description captures the breadth of the specification's role.

Consider an asphalt placement issue. The plan may show pavement limits and thickness. The specification framework may address mix design, production, temperature, placement, rolling, density, smoothness, sampling, lot acceptance, corrective action, and pay adjustments. A field decision based only on the plan thickness would therefore be incomplete.

The same is true for earthwork, concrete, drainage pipe, structural steel, pavement markings, signal equipment, lighting, and landscaping. The plan tells the team what and where. The specification often supplies much of the how well, how verified, and how accepted.

An engineer evaluating a suspected deficiency should therefore identify not only the drawing dimension but also the specification requirement that governs quality or acceptance. In many cases, the decisive question is not whether the work "looks right" but whether the specified property or test result has been achieved.

1.5 Standard plans and referenced criteria are part of the design language

Standard plans allow an agency to communicate recurring details efficiently. FDOT's Standard Plans, for example, are published separately and are used within contract plans under the Department's plans-development framework. A project plan may reference a standard plan instead of reproducing every dimensional or construction requirement.

That creates two coordination responsibilities. First, the project team must use the correct edition and applicable index. Second, project-specific notes or details may supplement or modify the standard arrangement. A field reviewer should not assume that a familiar standard detail applies exactly as remembered from a prior project.

Referenced criteria create the same issue. A note may incorporate a specification section, manual chapter, approved product list, testing standard, manufacturer's requirement, or permit condition. The physical sheet may contain only a short reference. The technical requirement lives partly outside the sheet.

A robust document-review process therefore treats references as active links in the requirement chain. If a critical decision depends on a referenced requirement, obtain and verify the referenced source rather than relying on memory.

1.6 Quantities and schedules are coordination tools, not substitutes for geometry

Transportation plan sets often include pay-item quantities, summary tables, signal equipment schedules, sign tables, drainage summaries, pavement-marking quantities, utility schedules, and other tabular information. These tables are valuable coordination tools, but they can conflict with plan geometry or details if revisions are not carried through every location.

A common example is a quantity table that reflects an earlier design while the plan view has been revised. Another is a sign schedule that lists one post type while a detail or standard plan requires another based on size or location. A drainage summary may show a structure size that does not match a later profile revision. The field team should not resolve such discrepancies by selecting whichever entry is easier to build.

When a quantity, schedule, drawing, and specification appear inconsistent, treat the conflict as a coordination issue. Determine which document controls under the contract, identify whether the inconsistency changes design intent, and route the issue through the required clarification or change process.

The practical lesson is that tables support coordination; they do not relieve the engineer of interpreting the complete requirement.

1.7 Approved submittals add construction-specific information

Submittals, shop drawings, product data, samples, mix designs, catalog information, fabrication drawings, and calculations translate general contract requirements into construction-specific information. They may show dimensions, components, materials, fabrication details, equipment characteristics, or installation information that was not practical to include in the design documents.

Approval or review of a submittal does not automatically rewrite the contract documents. The scope of review is defined by the contract and professional role. An approved shop drawing can become important construction information, but a deviation from the contract should be clearly identified and validly accepted rather than hidden within hundreds of shop-drawing dimensions.

A useful submittal review asks four questions:

1. Does the submittal satisfy the stated contract requirement? 2. Does it identify any deviation from the contract documents? 3. Does the deviation affect another discipline, interface, or design assumption? 4. Has the person with authority to accept or design the deviation actually done so?

This distinction becomes critical when the field later discovers that installed work matches the shop drawing but not the contract plan. The project must determine whether the shop-drawing condition was an approved design change, an overlooked deviation, or an installation error. The word "approved" alone does not answer that question.

1.8 RFIs are clarification tools, not informal redesign mechanisms

Requests for information are essential when the contract documents contain an ambiguity, omission, conflict, or condition that cannot reasonably be resolved by the field team within its authority. A well-written RFI identifies the location, the documents reviewed, the specific conflict, the question requiring resolution, and the schedule impact if known. It may propose a solution, but the proposal should be clearly distinguished from the question.

Weak RFIs transfer unnecessary interpretation to the responder: "Please advise" with no document references, no field measurements, and no description of the conflict. Strong RFIs reduce decision latency because the technical problem is already framed.

The response should also be classified. A response may:

- clarify an existing requirement without changing design intent;
- confirm a permissible interpretation already contained in the documents;
- provide missing design information;
- reject a proposed alternative;
- direct the issue into a formal change process; or
- identify that additional information or interdisciplinary review is required.

The project should avoid using an RFI response as an undocumented substitute for a required sealed design revision or formal contract change when the response actually changes design intent, quantities, scope, or technical criteria.

1.9 Field directives and change documents must be distinguishable from discussion

Transportation construction moves quickly, and many technical conversations occur in the field. The problem arises when a discussion becomes an instruction without the documentation required by the project. "Move it two feet so it clears" may sound practical, but a two-foot move can affect drainage, accessibility, utility separation, sight distance, signal timing equipment, structural support, maintenance access, or right-of-way constraints.

A reliable change process separates three stages:

Observation or issue: A conflict exists.

Technical disposition: A qualified, authorized person determines the acceptable technical resolution.

Implementation authorization: The project issues the documentation required for construction, cost, schedule, and record purposes.

Those stages may occur rapidly, but they should remain conceptually distinct. A field engineer can identify the problem without having authority to change the design. An EOR can determine the technical solution without having contractual authority to authorize extra cost. A contractor can propose a means of resolving the issue without being able to approve a permanent design change.

1.10 Recognizing incomplete or ambiguous requirements

Not every missing dimension is a design error. Some dimensions are intentionally derived from geometry, standard details, or field fit-up. The key is whether the information available allows the work to be built and inspected without unsupported assumptions.

Potential ambiguity indicators include:

- two sheets show different dimensions for the same feature;
- a profile elevation conflicts with a structure table;
- a note references a standard plan that does not match the depicted configuration;
- a specification and plan note require different materials;
- a utility conflict is visible when disciplines are overlaid but not addressed in either discipline's notes;
- a pay item appears in quantities but no corresponding work is shown;
- a shop drawing introduces a geometry change not identified as a deviation;
- a field condition differs materially from the survey or geotechnical information used in design; or
- the only way to proceed is to assume a value that affects performance, safety, durability, or compliance.

The appropriate response is not to stop every time a minor discrepancy is noticed. It is to determine whether the discrepancy is material to the technical outcome and whether the field team has authority to resolve it.

1.11 Order of precedence does not eliminate engineering judgment

Many contracts establish an order of precedence for conflicting documents. That contractual rule is important, but it should not be used mechanically when the higher-priority document appears to create an unsafe, impossible, or clearly unintended result.

Suppose a specification takes precedence over a drawing, but applying the specification literally would require a drainage pipe material that is incompatible with a project-specific connection detail. The order-of-precedence clause may identify which requirement governs commercially, but the technical inconsistency still deserves review. The project should not rely on a contract clause to avoid asking whether the governing interpretation is physically and technically coherent.

Similarly, a plan note may control over a standard detail, yet the plan note may have been copied from an earlier design stage and may no longer reflect the intended system. Good engineering combines contract interpretation with technical plausibility.

A useful rule is: use the precedence clause to route the conflict, not to suppress the conflict.

1.12 Conformance must be stated against a defined requirement

Inspection language becomes stronger when it identifies the exact requirement. Compare:

Weak: "Pipe installation appears acceptable."

Better: "At Sta. 145+72, Structure S-14 to S-15, the installed 24-inch pipe was observed at the plan alignment. Measured upstream invert elevation was 18.42 ft; approved plan elevation is 18.40 ft. Joint condition and bedding were documented photographically. Material markings corresponded with the approved submittal."

The second statement provides evidence. It does not overstate acceptance. A separate contractual or engineering determination can decide whether the observed condition satisfies tolerance requirements.

The same approach applies to pavement thickness, concrete placement, compaction, signal equipment, markings, signs, utilities, lighting, and drainage. An auditable record identifies location, requirement, observed result, date, responsible parties, and the document used for comparison.

1.13 Document conflicts should be resolved before installation when reasonably possible

The cheapest nonconformance is the one prevented before work is installed. Constructability reviews, preconstruction meetings, discipline overlays, shop-drawing coordination, utility coordination, and pre-activity reviews all provide opportunities to identify conflicts before concrete is placed, pavement is compacted, cable is pulled, or traffic is shifted.

Pre-installation coordination is especially valuable for work that becomes concealed or difficult to alter. Drainage pipe under pavement, conduit crossings, signal foundations, bridge embedded items, utility sleeves, wall penetrations, and underground conflicts can be expensive to correct after subsequent work is placed.

A focused pre-activity document review should identify:

- controlling plan sheets and revision status;
- applicable specification sections;
- standard plans/details;
- approved submittals;
- unresolved RFIs;
- required tests or inspections;
- hold points or witness points;
- critical dimensions or elevations;
- interfaces with adjacent disciplines; and
- documentation required for acceptance.

This review converts the document set from a passive archive into an active construction-control tool.

1.14 A requirement trace can prevent disputed field decisions

For higher-risk or recurring work, a simple requirement trace can link the design requirement to the field evidence. The trace does not need sophisticated software. It can be a table that records:

- requirement source;
- requirement summary;
- location or work item;
- submittal or product approval;
- inspection/test method;
- acceptance criterion;
- evidence location; and
- disposition if the criterion is not met.

For example, a drainage run may be traced from plan profile to pipe specification, approved pipe submittal, bedding requirement, invert survey, installation photographs, test results if applicable, and final as-built record. When a later dispute arises, the project can reconstruct what requirement applied and what evidence supported closure.

Requirement tracing is particularly useful when several organizations contribute to acceptance. It reduces reliance on individual memory and makes turnover between personnel less disruptive.

1.15 Module application - classify the document before answering the question

Consider a field condition in which a proposed drainage structure conflicts with an existing utility. The contractor proposes moving the structure 3 feet downstream. Before deciding whether that is acceptable, the engineer should identify:

- the roadway and drainage sheets controlling location and profile;
- the utility information that creates the conflict;
- the standard plan governing the structure;
- any permit, hydraulic, maintenance, or right-of-way constraint;
- whether the move affects pipe slope, inlet spacing, gutter spread, structure depth, or adjacent work;
- whether the change is a clarification, field fit, or design change; and
- who has authority to approve and document the resolution.

The problem is not simply "can the structure move?" The problem is whether the coordinated transportation system still performs as intended after the move and whether the approved project record accurately reflects the decision.

1.16 Module takeaway

Transportation construction quality depends on a stable requirement baseline. Plans, specifications, standard plans, schedules, submittals, RFIs, and change documents must be interpreted as a coordinated system. Field personnel should use current approved documents, distinguish clarification from design change, and avoid informal directions that bypass required technical or contractual processes.

The engineer's strongest habit is to make every field conclusion traceable to a requirement. When the requirement is ambiguous, inconsistent, or incomplete, the ambiguity should be surfaced and resolved before it becomes installed work whenever reasonably possible.

1.17 Module practical checklist

- Verify the current approved plan and specification revision before relying on it.
- Read plan, profile/elevation, and section/detail together for multidimensional issues.
- Identify applicable standard plans and referenced criteria.
- Confirm that submittal approval did not conceal an undocumented deviation.
- Use RFIs for specific technical questions and distinguish clarification from change.
- Do not convert discussion into field direction without the required authorization.
- State observations against identifiable requirements rather than using vague acceptance language.
- Resolve material document conflicts before installation when reasonably possible.
- Trace critical requirements through inspection, testing, disposition, and closeout evidence.

MODULE 2 | 40 MINUTES

Multidisciplinary Plans, Specifications, Submittals & Coordination

Transportation projects compress many engineering systems into a narrow corridor. Roadway geometry, drainage, utilities, structures, traffic control devices, signing, pavement markings, lighting, landscaping, sidewalks, driveways, signals, communications systems, maintenance access, and right-of-way constraints may occupy the same physical space. Each discipline can be internally correct and still conflict with another discipline when the work is built.

The objective of multidisciplinary coordination is not to make every engineer an expert in every discipline. It is to identify interfaces early enough that the responsible disciplines can resolve them

deliberately. The most effective reviewer asks not only whether a feature satisfies its own plan, but also what else must occupy, cross, drain through, support, clear, or remain accessible at the same location.

2.1 Transportation coordination is an interface problem

INTERFACE	COORDINATION CHECK
Roadway and drainage	Grades, collection points, pipe slopes and outlet continuity
Utilities	Verified location, separation, protection and relocation sequence
Traffic / signals	Visibility, device placement, operation and access
Structures	Connections, supports, penetrations and geometry
Pedestrian / accessibility	Continuous usable route, slopes and clear space
Electrical / ITS	Conduit corridors, foundations, grounding and maintenance

An interface exists wherever one system's geometry, load, access, performance, sequence, or maintenance requirement interacts with another. A roadway grade establishes drainage elevations. Drainage structures influence curb and sidewalk geometry. Signal poles and sign supports compete with utilities, clear zones, sight lines, and pedestrian routes. Bridge work interacts with roadway approach grades, drainage, barriers, lighting, and utilities. Landscape plans can affect sight distance or utility access. Temporary traffic-control phases can restrict when permanent features may be installed.

The coordination problem is therefore spatial, temporal, and procedural.

Spatial interfaces involve physical conflicts such as a storm pipe crossing a utility at insufficient clearance.

Temporal interfaces involve sequence, such as a utility relocation that must be complete before excavation for a drainage structure.

Procedural interfaces involve approvals, permits, submittals, inspections, or information that one discipline needs from another before work can proceed.

A useful multidisciplinary review identifies all three rather than focusing only on geometric clashes.

2.2 Roadway and drainage coordination

Roadway and drainage are tightly coupled because roadway geometry controls where water travels and drainage design influences elevations, cross slopes, curb profiles, ditch grades, and outlet conditions. A small roadway change can have a disproportionate hydraulic effect.

Common coordination questions include:

- Does the inlet location correspond with the actual low point or gutter flow line?
- Do pipe slopes and structure inverts remain feasible after roadway-profile revisions?
- Does a driveway or curb-ramp tie-in interrupt the intended drainage path?
- Does a proposed utility conflict force a drainage structure move that changes spread, slope, or maintenance access?
- Do cross-drain elevations conflict with pavement structure, subgrade, or other utilities?
- Are ditch grades compatible with culvert elevations and outfall conditions?
- Does a revised median, curb line, or barrier alter inlet placement or pipe routing?

The reviewer should not treat drainage features as isolated dots on a plan. Follow water from the roadway surface through the collection system to the outlet. When a feature moves, ask what upstream and downstream assumptions move with it.

Coordination example - relocated curb inlet

A utility conflict makes the planned inlet location difficult to construct. Moving the inlet six feet may appear minor in plan view. But the move can change the distance to the sag point, local gutter spread, pipe length, pipe slope, structure depth, conflict with another lateral, or create a low area between the actual sag and the inlet. The correct review considers the hydraulic and geometric system, not merely whether there is room to place the structure.

2.3 Roadway and utility coordination

Utilities are a frequent source of construction-stage conflict because available information may represent records, survey observations, utility-owner information, potholing, or design assumptions of varying accuracy. Existing utilities can differ from their depicted locations. Proposed utility relocations can also change during coordination.

The project team should distinguish known, reported, and assumed utility information. A plan line is not proof that the utility is exactly at that depth or offset unless the project's investigation establishes that level of certainty. When critical clearance depends on utility location, the construction team may need verification before installing irreversible work.

Typical interface concerns include:

- drainage pipes crossing water, sewer, gas, power, or communications systems;
- signal or lighting foundations near existing utilities;
- sign supports within utility corridors;
- retaining-wall or barrier foundations affecting utility access;
- pavement excavation exposing shallow facilities;
- proposed utility elevations conflicting with drainage structures or roadway subgrade;
- valve, manhole, or handhole elevations that must match final grade; and
- utility work that must occur before or after other construction activities.

The engineering response to an unexpected utility should begin with documentation: exact location, elevation if available, size, apparent type, surrounding work, controlling plan information, photographs, and any immediate safety considerations. From there, the issue can be routed to the utility owner and affected design disciplines.

2.4 Traffic, signing, pavement marking, and roadway geometry

Traffic-control devices depend on roadway geometry and driver perception. A sign that is technically specified correctly can still be poorly coordinated if it conflicts with a signal head, tree, utility pole, roadside barrier, sidewalk, or sight line. Pavement markings depend on lane geometry, taper lengths, turn-lane configuration, and final pavement surface. Signal detection may depend on final lane placement or equipment geometry.

Coordination should consider not only installation location but also visibility, maintainability, and operational intent. A sign support placed to avoid a utility may become hidden by another feature. A signal cabinet relocated for constructability may reduce maintenance access. A pavement-marking transition may not align with a revised curb-return geometry. A mast arm foundation shift can change reach or equipment placement.

When field conditions require relocation, the team should determine whether the change remains within allowable installation tolerances or requires traffic engineering review. The field team should not assume that a few feet of relocation is harmless simply because the device is still in the general area.

2.5 Structures and roadway interfaces

Bridge and structural work introduces interfaces with roadway profiles, barriers, drainage, utilities, expansion joints, approach slabs, retaining systems, lighting, signs, and traffic-control phasing. Elevation control is especially important because small discrepancies can affect ride quality, joint geometry, deck drainage, barrier transitions, and approach grades.

A structure may also constrain adjacent utility or drainage routes. Penetrations, attachments, or supports that were not part of the structural design can create engineering questions. The field should not drill, core, weld, cut, or attach to structural elements based solely on convenience when the action could affect reinforcement, prestressing, fatigue, durability, or the load path.

An interface review should identify:

- connection points between roadway and structural geometry;
- transitions in barrier, railing, sidewalk, or shared-use-path systems;
- drainage transitions and deck outlets;
- embedded items and penetrations;
- utility attachments or crossings;
- access for inspection and maintenance; and
- sequence constraints that affect completion of the structural system.

2.6 Lighting, electrical, ITS, and underground congestion

Transportation corridors increasingly contain lighting, signal, intelligent transportation systems, communications, power, grounding, fiber, and control equipment. These systems create a dense underground network of conduits, pull boxes, handholes, foundations, grounding electrodes, and service connections.

The coordination challenge is often not visible in individual discipline plans. A lighting plan may show a pole and conduit route, while a signal plan shows another conduit system in the same shoulder. A drainage plan may place an inlet where several conduits must pass. A utility plan may reserve the same corridor. A sidewalk or curb ramp may leave insufficient space for access covers or equipment setbacks.

Before installation, field teams should review the combined corridor where practical. Digital overlays, coordinated stakeout, subsurface verification, and pre-installation meetings can reveal congestion that plan-by-plan review misses.

Where a conflict is discovered, the solution should preserve the functional requirements of all systems: bend radii, pull distances, grounding, separation, access, drainage, clearances, structural capacity, and future maintainability.

2.7 Pedestrian, bicycle, accessibility, and roadside interfaces

Transportation coordination must account for users beyond vehicles. Sidewalks, curb ramps, shared-use paths, detectable warnings, crosswalks, pedestrian signals, bicycle facilities, transit stops, drainage features, signs, poles, cabinets, and utility access points often occupy the same limited space.

A field adjustment intended to resolve one conflict can create an accessibility or operational issue. Moving a signal pole may affect pushbutton reach. Raising a utility cover may affect cross slope. Shifting an inlet may create a grate condition in a pedestrian path. Adjusting curb geometry may alter a ramp slope or landing. Relocating a sign can reduce sidewalk clear width.

The coordination process should therefore evaluate the complete user space. On critical pedestrian areas, dimensional verification before concrete placement can prevent expensive removal and replacement.

2.8 Submittal review versus design responsibility

Submittal review is one of the most misunderstood multidisciplinary interfaces. A contractor or supplier may provide shop drawings, product data, fabrication drawings, mix designs, calculations, installation instructions, or other information. The reviewer typically checks conformance with the design concept and contract requirements within the reviewer's assigned scope. The review does not automatically transfer the contractor's coordination obligations, fabrication responsibility, or delegated-design responsibility to the reviewer.

A reviewer should focus on the interfaces that matter to the permanent project:

- overall dimensions and fit;
- design loads or performance requirements;
- connection points to permanent work;
- materials and specified properties;
- clearances;
- compatibility with adjacent systems;
- identified deviations; and
- information that another discipline must verify.

The reviewer should avoid spending effort on fabrication details that are outside the review scope while missing a deviation that changes the permanent design.

Practice point - highlight deviations explicitly

A deviation buried in a shop drawing can be missed even during diligent review. The project should require proposed deviations to be clearly identified. When a deviation affects another discipline, route it to that discipline rather than assuming the primary reviewer will detect every secondary consequence.

2.9 Product substitutions are multidisciplinary decisions

A proposed substitute may match the nominal function of the specified product yet differ in dimensions, weight, power demand, anchorage, drainage behavior, durability, maintenance, control interface, or installation method. Substitution review should therefore address both equivalence and interface effects.

For example, a substitute signal cabinet may satisfy functional requirements but have a larger foundation footprint. A drainage product may have different wall thickness or joint geometry. A lighting fixture may change electrical load or mounting requirements. A proprietary barrier transition may require different anchorage. A pavement marking material may have different surface-preparation or curing requirements.

The review should identify:

1. What requirement is the substitute intended to satisfy? 2. What properties differ from the specified product? 3. Do those differences affect another discipline or constructed interface? 4. Is additional testing, certification, calculation, or approval required? 5. How will the approved substitution be captured in construction and record documents?

Approval without record integration creates a later closeout problem because the installed condition may not match the original documents even though it was authorized.

2.10 RFIs should define the physical conflict precisely


A multidisciplinary RFI is most useful when it describes the physical conflict in a way that all affected disciplines can understand. Generic statements such as "utility conflicts with drainage" force the reviewer to reconstruct the problem.

A stronger RFI might state:

"At Sta. 312+45, the proposed 36-inch storm pipe from S-22 to S-23 crosses an existing 8-inch water main. Field potholing indicates top of water main El. 24.86 ft. Proposed storm invert at crossing is El. 25.05 ft, leaving insufficient vertical separation for the depicted configuration. Attached survey points and photographs document the condition. Contractor requests direction on whether to revise storm profile, relocate structure S-23, or coordinate utility adjustment."

This formulation provides location, measured evidence, controlling design information, and the decision required. The engineer can then evaluate the issue without first requesting basic facts.

2.11 Clarification versus change in design intent



Clarification and design-change pathways converge at issue, distribution and verification controls.

Not every RFI response is a design change. A clarification explains how an existing requirement is to be interpreted. A design change alters geometry, materials, performance criteria, scope, or another technical element of the approved design.

The distinction matters because changes may require additional calculations, sealed revisions, owner approval, permit coordination, quantity changes, cost/schedule action, or updates to record documents.

A useful test asks: If the response were incorporated into the plans, would the design show something materially different from the currently approved intent? If yes, the issue likely belongs in the controlled change process rather than being treated as a simple clarification.

Examples of likely clarification:

- identifying which of two notes applies when the intended configuration is already clear from the complete document set;
- confirming a standard detail referenced by the plans; or
- providing a missing dimension that can be derived directly from established geometry.

Examples more likely to be design changes:

- moving a drainage structure enough to change hydraulic geometry;
- changing pipe size or material outside permitted alternatives;
- relocating a signal support in a way that changes equipment layout;
- modifying barrier transitions; or
- accepting a product with different structural or operational characteristics.

2.12 Digital coordination helps but does not replace engineering review

CADD overlays, three-dimensional models, utility models, GIS, clash-detection tools, point clouds, and digital field platforms can expose conflicts that are difficult to see on separate sheets. These tools are valuable because they bring disciplines into a common spatial frame.

However, a detected clash is not automatically an engineering problem, and the absence of a digital clash is not proof of coordination. Models can contain inaccurate utility elevations, simplified object sizes, missing tolerances, or outdated design information. A conduit represented by a line may have a real installation envelope. A sign pole modeled correctly may still create a sight-distance issue that geometric clash software does not understand.

Digital coordination is most effective when paired with engineering questions about function, performance, construction tolerance, maintenance, and sequence.

2.13 Tolerances and field fit-up require context

Transportation construction cannot be performed to zero tolerance. Specifications, standard plans, and accepted construction practice allow some variation. The challenge is determining whether a particular variation is within an applicable tolerance, requires adjustment, or changes design intent.

A field-fit decision should consider:

- the explicit tolerance if one exists;
- cumulative tolerance with adjacent features;
- whether drainage or operational performance is sensitive to the variation;
- whether accessibility criteria are affected;
- whether the variation changes clearances or cover;
- whether the variation affects another discipline; and
- whether the installed condition remains documentable and maintainable.

The presence of a tolerance does not mean every feature can be shifted independently. Several individually acceptable shifts can accumulate into a system-level conflict.

2.14 Constructability coordination should focus on irreversible work

Not all interfaces deserve the same attention. Risk-based coordination concentrates effort on work that is expensive to alter, becomes concealed, controls subsequent activities, or affects safety or public operation.

High-value coordination targets include:

- underground crossings before backfill;
- drainage structure and pipe elevations before pavement;
- signal and lighting foundations before pole delivery;
- embedded conduit before concrete placement;
- bridge deck embedded items;
- utility sleeves through structural or retaining elements;
- curb-ramp geometry before finishing; and
- final roadway elevations before surface-course placement.

These items benefit from hold points, field verification, or multidisciplinary sign-off because correction becomes disproportionately expensive after subsequent work is installed.

2.15 Coordination meetings should produce decisions, not merely discussion



A useful coordination meeting leaves an issue owner, due date, technical decision path, and final document reference. Contextual illustration, not a documented project record.

A coordination meeting is effective when it produces an actionable record. For each issue, the record should identify:

- issue location and description;
- documents reviewed;
- affected disciplines;
- information still needed;
- responsible decision-maker;
- target date;
- interim work restriction if applicable; and
- final disposition/document reference when resolved.

This converts coordination from a recurring conversation into a controlled issue-management process. Open items should be carried forward until closure, and closure should reference the actual RFI, plan revision, submittal, change document, or other evidence.

2.16 Interface risk increases when authority is unclear

Many multidisciplinary conflicts persist because the technical question has no clear owner. The roadway engineer assumes drainage will resolve it. Drainage assumes utilities will move. Utilities assume the contractor will field-fit. The contractor assumes the inspector can approve a minor adjustment. The inspector documents the issue but lacks authority to redesign.

A simple escalation map can prevent this drift. Define which role can:

- interpret existing requirements;
- issue design clarifications;
- approve substitutions;
- change permanent design;
- authorize cost or schedule changes;
- accept nonconforming work; and
- close quality records.

The map must reflect the actual contract. Its value is in making decision pathways explicit before a conflict occurs.

2.17 Applied coordination scenario - signal foundation and drainage conflict

A signal strain-pole foundation is staked according to the signal plans. During excavation layout, the contractor identifies a storm pipe passing through the proposed foundation footprint. The storm line cannot be moved easily because it connects two structures with limited slope. Moving the pole may affect mast-arm reach, signal-head placement, pedestrian pushbutton location, clear zone, and underground conduit.

A poor response is to shift the pole a few feet in the field and update the sketch later. A disciplined response is to document the conflict and bring the affected information together:

- signal plan and pole schedule;
- storm-drain plan/profile;
- foundation detail;
- utility/conduit layout;
- pedestrian features;
- roadway geometry and clearances;
- applicable standard plans; and
- field survey/stakeout information.

The signal/traffic designer, drainage engineer, and other affected parties can then evaluate alternatives. The final solution may be a pole relocation, drainage adjustment, revised foundation, or other engineered change. The important point is that the decision is coordinated and recorded before irreversible work occurs.

2.18 Applied coordination scenario - utility adjustment at curb ramp

An existing communications handhole falls within the limits of a proposed curb ramp. The utility owner proposes raising the lid to match finished grade and leaving it in place. That solution may preserve the utility but can affect the ramp's running slope, cross slope, detectable-warning placement, smoothness, drainage, and pedestrian clear space.

The correct review does not ask only whether the handhole can be raised. It asks whether the complete accessible route remains compliant and constructible. If not, the utility adjustment may need relocation or a coordinated ramp redesign. This is a classic example of a small utility decision becoming a roadway/accessibility design issue.

2.19 Module takeaway

Multidisciplinary coordination is the practice of managing interfaces. Roadway, drainage, utilities, traffic, structures, lighting, signals, pedestrian facilities, and other systems interact spatially and operationally. Submittals, RFIs, substitutions, digital models, and field measurements provide additional information, but they do not eliminate the need for defined authority and controlled design decisions.

The most effective engineer looks across discipline boundaries, prioritizes irreversible work, distinguishes clarification from design change, and makes sure that approved resolutions are carried into the construction and record documents.

2.20 Module practical checklist

- Identify spatial, temporal, and procedural interfaces for major work activities.
- Coordinate roadway and drainage as one elevation-controlled system.
- Verify critical utility locations when design decisions depend on them.
- Check traffic-control-device relocations for visibility, operation, access, and clearances.
- Review structural interfaces before drilling, coring, attaching, or modifying permanent work.
- Overlay underground electrical/ITS/conduit systems where congestion is likely.
- Protect pedestrian and accessibility requirements when resolving field conflicts.
- Require deviations in submittals and substitutions to be clearly identified.
- Write RFIs with location, evidence, document references, and a specific question.
- Route design changes through the appropriate controlled process.
- Use digital clash detection as a coordination aid, not as proof of engineering adequacy.
- Focus hold points on concealed, irreversible, or high-consequence interfaces.
- Carry open coordination issues to documented closure.

MODULE 3 | 45 MINUTES

Construction-Phase Information, Field Coordination & Documentation

Construction-phase engineering depends on information that is created continuously as work is installed. The plan set establishes requirements, but the field produces the evidence needed to determine what actually happened: observations, measurements, survey data, inspection reports, material certifications, photographs, testing results, contractor reports, equipment records, correspondence, and change documentation. The professional challenge is to turn that stream of information into decisions without overstating what the evidence proves.

The central discipline in this module is the separation of fact, interpretation, and disposition. A field record should first establish facts. Technical personnel then interpret those facts against requirements. Finally, the person with authority decides whether the work conforms, requires correction, needs engineering evaluation, or can be accepted under an approved deviation. When those stages are compressed into one undocumented judgment, projects lose traceability and create unnecessary professional risk.

3.1 Field observation is evidence, not automatic acceptance

EVIDENCE STAGE	TECHNICAL FUNCTION
Observe	Record the physical condition and limits of observation
Measure / test	Identify location, method, represented work and result
Compare	State the current applicable requirement
Evaluate	Use competent interpretation and defined authority
Disposition	Document the authorized technical response
Verify / record	Confirm implementation and preserve its evidence

Engineers, inspectors, construction managers, and owner representatives often observe work in progress. An observation can confirm location, apparent condition, dimensions, work sequence, presence of materials, visible defects, or completion of a specified activity. It does not automatically establish every property of the work.

For example, observing concrete placement can establish that reinforcement was visible before placement, forms were in place, and concrete was delivered. It does not by itself establish compressive strength, air content, slump, curing adequacy, or long-term durability. Those properties may require tests, certifications, or later evidence.

Similarly, observing a drainage pipe after installation may establish alignment, visible joint condition, and approximate bedding. It does not necessarily prove compaction quality around concealed portions after backfill.

Good field documentation therefore states what was actually observed. Avoid language such as "all work acceptable" when the observer reviewed only a limited portion or when acceptance depends on separate testing.

3.2 Inspection should be planned around risk and verification opportunity



Inspection is most valuable when performed before critical work is concealed or becomes expensive to correct. Contextual illustration, not a documented project record.

Inspection resources are finite. A mature inspection plan concentrates attention where the project has the greatest need for verification: work that will be concealed, high-consequence features, activities with known quality sensitivity, specification-defined hold points, first-production activities, and interfaces likely to generate disputes.

A risk-based inspection plan asks:

- What requirement must be verified?
- When is the best opportunity to observe it?

- What evidence will remain after the work is concealed?
- What testing or measurement is required?
- Who must be present or notified?
- What condition prevents the work from advancing?
- What records are needed for final acceptance?

For underground work, the best inspection opportunity is often before backfill. For reinforcement, it is before concrete placement. For pavement layers, it is before the next layer covers the surface. For signal conduit, it may be before trench closure and before foundations or pull boxes are inaccessible.

3.3 Hold points and witness points create deliberate pauses



Hold points are project-defined. A witness opportunity is not automatically a mandatory hold.

Inspection before concealment, with a project-defined hold and release.

A hold point is a defined condition at which work should not proceed until a specified review, test, approval, or verification has occurred. A witness point gives a designated party the opportunity to observe an activity without necessarily stopping the work if that party elects not to attend, subject to the project's procedures.

Hold points are most valuable when later correction would be expensive or when a hidden condition controls long-term performance. Examples may include:

- verifying subgrade or foundation conditions before placement;
- confirming reinforcement and embedded items before concrete;
- verifying critical elevations before closing an underground system;
- reviewing failed test dispositions before covering the work;
- confirming temporary traffic-control readiness before a major traffic shift; or
- verifying correction of a critical deficiency before reopening a facility.

The point is not to create paperwork. The point is to ensure that a decision is made while the evidence is still visible and the work is still correctable.

3.4 Measurements should be reproducible

A measurement is more useful when another person can understand how it was obtained. Field notes should identify the location, reference system, instrument or method where relevant, units, date, and the feature measured.

Transportation work often uses station/offset, northing/easting, elevation, lane designation, structure number, pole number, sign number, or other project-specific identifiers. A note that simply says "pipe high by 0.2" is weak. A reproducible record might state:

"S-14 upstream invert, 24-inch pipe to S-13, measured El. 18.42 ft using project control benchmark BM-7; approved plan invert El. 18.40 ft. Survey point file attached."

This level of detail supports later engineering review and reduces disagreement over what was measured.

3.5 Photographs should carry technical context

Photographs are powerful because they preserve visual evidence after the work is covered or modified. They are weak when the viewer cannot identify location, scale, orientation, date, or significance.

A useful photographic record may include:

- overview image showing project context;
- closer image showing the condition;
- scale or measurement reference where appropriate;
- station/offset, structure number, or other location identifier;
- direction of view;
- date and time;
- annotation or caption identifying the technical issue; and
- linkage to the inspection report, RFI, deficiency record, or test result.

Avoid relying on metadata alone. Image metadata can be stripped when files are transmitted. The project record should preserve the context in a caption or associated report.

Practice point - photograph before disturbance

When a possible deficiency is discovered, document the original condition before repair, excavation, demolition, or cleaning changes the evidence, provided doing so does not interfere with safety. The "before" condition may be essential for engineering evaluation.

3.6 Testing results are technical evidence with limits

Material and field tests provide quantitative evidence, but a result must be interpreted within the test method, sampling plan, acceptance specification, and represented lot or work area. One passing test does not necessarily prove an entire project conforms. One failing test does not automatically prove every nearby area is deficient.

The reviewer should understand:

- what property the test measures;
- how the sample or test location was selected;
- what quantity of work the result represents;
- acceptance threshold or statistical framework;
- test method and equipment requirements;
- whether the result is valid or questionable;
- retest or investigation provisions; and
- how the result affects acceptance or corrective action.

For density/compaction testing, for example, the project may define lots, test frequencies, target densities, moisture considerations, and retest procedures. For concrete, strength specimens represent specific placements under defined sampling and curing conditions. For asphalt, acceptance may involve multiple characteristics and lot-based evaluation.

3.7 Distinguish field facts from engineering conclusions

This distinction is worth practicing explicitly.

Fact: "Crack approximately 0.08 inch wide observed at the southeast corner of the concrete barrier end transition at Sta. 522+14."

Interpretation: "Crack appears to extend through the surface mortar and may be associated with restraint at the transition."

Disposition: "EOR evaluation required before acceptance; do not apply repair material until crack extent is documented."

The first statement is observational. The second is a technical interpretation that should be supported by competence and evidence. The third is an action decision based on project authority.

Separating the categories allows several people to contribute without accidentally assigning professional responsibility to the wrong role.

3.8 Inspection reports should answer a future reader's questions

A strong inspection report should remain understandable months or years later. A future reader should be able to determine what work was underway, what was observed, what requirements were checked, what deficiencies were identified, and what follow-up remained open.

Useful report elements include:

- date, weather, and work shift if relevant;
- inspector/observer identity;
- contractor and crews performing the work;
- exact location and activity;
- controlling documents or specifications checked;
- materials and equipment observed;
- test references;
- measurements;
- photographs;
- deficiencies or unusual conditions;
- instructions or notifications made within authority;
- RFIs, nonconformance reports, or change documents initiated; and
- unresolved follow-up items.

Reports should avoid unsupported legal conclusions or broad certifications beyond the observer's scope.

3.9 Communication should match authority

Construction teams need fast communication, but technical speed does not justify ambiguous authority. A field representative may be authorized to reject visibly defective work, request correction, or stop a specific activity under the contract. Another representative may only document and notify. An EOR may have authority to interpret design intent but not to authorize extra compensation. An inspector may confirm that work matches a dimension but not approve a redesign.

Communications should therefore use verbs carefully. "Observed," "measured," "notified," "requested," "recommended," "accepted," "approved," "certified," and "directed" carry different implications.

When authority is limited, say so plainly. For example:

"Condition documented and referred to the Engineer of Record for technical evaluation. No disposition is provided by this field observation."

This is not evasive language. It preserves the decision pathway.

3.10 Verbal discussions should be memorialized when technically significant

Many useful decisions begin in a site conversation or phone call. If the conversation affects design interpretation, corrective work, schedule restrictions, acceptance, or another significant technical matter, it should be memorialized in the project record.

A concise confirmation may state:

- participants;
- issue discussed;
- key facts available;
- decision or action agreed;
- responsible party;
- due date; and
- formal document that will follow if required.

The purpose is to prevent later disagreement and to make sure that all affected disciplines receive the same information.

3.11 Daily reports and specialty records should be linked, not isolated

Transportation projects generate many record types: daily inspection reports, testing reports, survey files, environmental records, maintenance-of-traffic inspections, pile-driving records, concrete placement reports, welding/NDT reports, traffic-signal checklists, utility records, and material certifications.

The project quality file is stronger when those records can be linked to the work item and any resulting issue. A failed density test should connect to the location, lot, corrective action, retest, and final closure. A drainage elevation discrepancy should connect to survey data, RFI, design response, revised plan, and as-built record.

Without linkage, the project may possess all required documents but still lack a clear story of what happened.

3.12 Field conditions can invalidate design assumptions

Construction occasionally reveals conditions that differ from the information available during design: unexpected utilities, unsuitable soil, groundwater, damaged existing infrastructure, undocumented structures, different existing grades, or previously modified facilities.

The first response is not automatically redesign. The first response is to document the discovered condition accurately and compare it with the design assumption. The project should then determine whether the difference is material.

Important documentation may include:

- exact location and limits;
- dimensions/elevations;
- photographs;
- samples or test results;
- existing-condition drawings or survey information;
- safety implications;
- affected work; and
- temporary protective actions.

The EOR or appropriate discipline can then determine whether the original design remains valid or requires modification.

3.13 Nonconforming observations should be documented neutrally

An inspection record should not become a negotiation. When a condition appears not to conform, document the requirement and observed condition objectively.

Instead of: "Contractor installed pipe wrong again."

Use: "At Sta. 322+18, pipe segment S-31 to S-32 measured 1.4 ft left of approved plan centerline at the midpoint. Plan centerline and field survey points attached. Condition referred for evaluation because revised alignment may affect utility clearance and structure connection geometry."

Neutral language improves technical credibility and reduces conflict. It focuses discussion on evidence and requirements rather than blame.

3.14 Temporary fixes should not become undocumented permanent dispositions

Construction teams sometimes implement temporary protective measures while a technical issue is under review: cover a hole, support a component, barricade an area, protect exposed reinforcement, pump water, place temporary markings, or restrict traffic.

The record should clearly identify the measure as temporary and define what still must occur before final acceptance. Otherwise, the project may later treat the temporary condition as if it were the approved resolution.

A temporary-action note should identify:

- immediate hazard or exposure being controlled;
- temporary measure installed;
- date/time;
- person authorizing the temporary action;
- limitations or monitoring requirements; and
- pending engineering/contractual disposition.

3.15 Repeated observations can reveal a systemic issue

One isolated defect may be corrected locally. Repeated similar defects may indicate that the work process, material, equipment, layout method, supervision, submittal, or interpretation is wrong.

Field data should therefore be reviewed for patterns. Examples include:

- repeated low density in the same material or equipment cycle;
- recurring drainage invert deviations;
- repeated signal-foundation conflicts;
- multiple pavement-marking alignment issues;
- recurring concrete surface defects;
- repeated missing documentation for the same subcontractor; or
- multiple installations based on an outdated drawing.

Trend recognition is not just a quality-management function. It can prevent the project from repeatedly repairing symptoms while leaving the cause active.

3.16 Digital field tools improve speed but require data discipline

Tablets, mobile inspection applications, cloud photo systems, digital plan viewers, geotagged forms, and issue-tracking platforms can improve access and traceability. They can also create new risks if naming, versioning, permissions, or synchronization are poorly controlled.

A digital field system should answer:

- Which plan revision is the user viewing?
- Are offline copies synchronized?
- How are photographs linked to locations and issues?
- Can records be edited after submission, and is revision history retained?
- Are signatures or approvals distinguishable from simple acknowledgments?
- Can records be exported and retained for the required period?

Technology should strengthen the evidence chain rather than merely increase the volume of data.

3.17 The field record should support engineering evaluation



Complete field packages shorten engineering response time by combining location, requirement, measurements, photographs, and the specific question. Contextual illustration, not a documented project record.

When an issue is escalated to an engineer, the field package should contain enough information for a meaningful evaluation. A high-quality package often includes:

- concise problem statement;
- controlling requirement;
- measured or observed deviation;
- plan excerpts;
- photographs;
- survey or test data;
- affected adjacent work;
- contractor's proposed disposition if any;
- schedule constraints; and
- questions requiring decision.

This reduces repeated requests for basic information and shortens decision time without compromising rigor.

3.18 Applied example - questionable drainage invert

An inspector observes that a newly installed inlet appears higher than expected. The structure has not yet been backfilled fully.

A disciplined response is:

1. Preserve the condition for measurement if practical. 2. Obtain survey elevations using project control. 3. Identify plan inverts, structure number, pipe size, and connected system. 4. Document pipe slope and adjacent structure elevations. 5. Photograph the installation before concealment. 6. Determine whether the measured condition is within applicable tolerance or changes hydraulic function. 7. If engineering review is required, provide the full field package. 8. Do not complete irreversible cover work until the required disposition is obtained.

The result may be acceptance within tolerance, adjustment, removal/reinstallation, profile revision, or another solution. The field record supports whichever decision is made.

3.19 Applied example - damaged installed conduit

During grading, construction equipment damages a conduit bank that has already passed an earlier inspection. The visible damage is repaired by the electrical subcontractor before the field engineer arrives.

The record should not begin with the repair. It should reconstruct the original damage: photographs if available, location, conduit type and contents, extent of damage, repair method, manufacturer or specification requirements, testing performed after repair, and whether the repair affects future pullability, insulation, grounding, or watertightness.

The engineering or contractual disposition can then be based on evidence rather than on the statement that "it was fixed."

3.20 Applied example - observation versus certification

An owner representative attends a pavement-marking installation and notes that markings appear aligned and continuous. The contract requires specific material, thickness, bead application, and retroreflectivity performance.

The observer can document visible alignment and workmanship. Acceptance of the installed marking may also require material records, application data, test results, or later performance measurements. A report saying "markings approved" would overstate what the observation established.

3.21 Module takeaway

Construction-phase information becomes engineering evidence only when it is specific, traceable, and interpreted within the requirement framework. Observations, photographs, measurements, tests, and

reports should establish facts without implying conclusions they do not support. Hold points should preserve verification opportunities. Significant verbal decisions should be documented. Repeated defects should be trended. Digital tools should preserve revision and audit history.


The professional objective is a record that allows another qualified person to understand what requirement applied, what was observed or measured, what decision was made, who made it, and what evidence supports closure.

3.22 Module practical checklist

- Plan inspection around concealment, consequence, and specification requirements.
- Use hold points for work that should not advance before verification.
- Record measurements with location, units, reference system, and method.
- Capture photographs with location, orientation, date, and technical context.
- Understand what each test result represents and what it does not represent.
- Separate field facts from interpretation and disposition.
- Write reports so a future reader can reconstruct the event.
- Use verbs that match actual authority.
- Memorialize technically significant verbal decisions.
- Link daily reports, tests, photographs, RFIs, deficiencies, and change records.
- Document differing field conditions before they are disturbed when practical.
- Identify temporary measures as temporary and track final disposition.
- Trend repeated defects for systemic causes.
- Preserve version and audit history in digital field systems.
- Send complete evidence packages when requesting engineering evaluation.

Coordination evidence: closing a utility conflict

The FHWA SHRP2 Kentucky case describes a utility coordination system that connects utility information with project records and status. The embedded KURTS interface shows a project identity, mapped conflict and status-linked table. Those are useful record connections; a displayed status alone does not establish how the installed condition was verified.



1 Project / location identity 2 Mapped conflict 3 Status-linked record

Source interface, not our worked example. A status value does not independently prove field closure.

Documented coordination interface. FHWA SHRP2 Kentucky case study, p. 1; screenshot credited to KYTC. Numbered callouts added by BuilderCE. The historical screen is a system example, not the case record completed below.

Source: FHWA SHRP2, Managing Utility Conflicts in Kentucky. Open original publication


A technical response can resolve the design question while the field condition remains unchanged. Closure also requires issuance of revised information to the people performing the work and evidence that the actual installation or clearance was checked. The published case is a system implementation example, not a complete resolved RFI file.

Worked coordination record: UC-17

The following completed record is an illustrative teaching example. Its identifiers, elevations, criteria and outcomes are supplied assumptions, not Kentucky project data or generally applicable utility-separation rules. It continues the drainage-and-utility coordination problem used in the course.


RECORD	ESTABLISHED INPUT
Location and baseline	UC-17; Sta. 145+72. Drainage sheet D-12 Rev. 0; utility sheet U-04 Rev. 1; common project vertical datum.
Observed condition	Field survey FS-17 identifies utility exterior bottom El. 22.40 ft at the crossing. Survey references and photographs P-17A/B are retained.
Design exterior surface	The storm pipe outside top is El. 21.90 ft, established from the specified pipe outside dimensions and design profile, not from its nominal diameter alone.
Illustrative governing criterion	This example assumes a project-approved minimum exterior-to-exterior separation of 1.00 ft. That value must be replaced by the actual applicable requirement on a real project.
Initial control	Do not install or backfill the affected crossing pending technical resolution; unrelated work may proceed under its own controls.

UC-17 | PLAN AND CROSSING SECTION



D-12 / U-04: same crossing at Sta. 145+72

SECTION AT CROSSING



Schematic only; project datum and measured exterior surfaces must agree.

Annotated teaching sketch. Plan views must identify the same crossing; the section tests the vertical interface using exterior surfaces. Geometry is schematic, not a construction detail.

Calculate the conflict and frame the RFI

STEP	CALCULATION / DECISION
Existing gap	22.40 − 21.90 = 0.50 ft exterior-to-exterior separation.
Required change	1.00 − 0.50 = 0.50 ft additional separation is needed under the supplied criterion.
Design implication	An illustrative alternative lowers the storm outside top to El. 21.40 ft: 22.40 − 21.40 = 1.00 ft. Matching the minimum is a geometric boundary, not a construction tolerance allowance.
Limits of this arithmetic	This calculation does not establish hydraulic adequacy, cover, bedding, connected inverts, utility protection, available construction tolerance or approval. Those effects require the responsible disciplines.

RFI-017 states the crossing location, current sheets and revision identifiers, measured utility surface, storm exterior surface, datum, calculated shortfall and work restriction. It requests a coordinated resolution and identifies FS-17 and P-17A/B as attachments. The contractor may describe alternatives but cannot convert the request into a permanent-design approval.

Record the decision, issue it and verify the result

STAGE	COMPLETED TEACHING RECORD	CLOSURE EVIDENCE
Issue identified	UC-17 / RFI-017 links the 0.50-ft shortfall to the affected crossing.	FS-17, P-17A/B, D-12 Rev. 0 and U-04 Rev. 1 retained.
Technical response	For this example, the drainage EOR and utility owner accept an engineered profile change after checking hydraulics, connected inverts, cover, protection and tolerances. The issued detail sets a storm outside-top target of El. 21.30 ft and allowable range 21.25–21.35 ft.	Calculation C-17, utility concurrence U-17 and the authorized change record define the configuration and limits; these are assumed example records.
Information issued	D-12 Rev. 1 and coordinated U-04 Rev. 2 supersede the affected previous details; distribution transmittal T-17 identifies receiving field teams.	The formal project change authorizes implementation; RFI-017 is cross-referenced rather than treated as authorization by itself.
Field verified	Before backfill, FS-18 records utility bottom 22.40 ft and storm outside top 21.32 ft using the same datum. Gap = 1.08 ft; storm elevation is within the supplied range.	P-18A/B, inspection I-17 and FS-18 document the crossing. The authorized party releases only the verified affected work.
Record closed	UC-17 closes after installation evidence, required acceptance records and record-drawing update RD-17 are linked.	Record information identifies the installed elevations, source observations and authorized revision; the original issue remains in history.

The revised target creates a 0.10-ft nominal margin above the example minimum. At the highest permitted storm top, the assumed utility bottom gives 22.40 − 21.35 = 1.05 ft separation. This is not a universal allowance: measurement uncertainty, utility movement and construction variation must fit the actual project criteria. Any changed field elevation or configuration reopens the affected check before concealment.

The decision rests on four distinct evidence stages: the issue is identified; a technically authorized response is established; the applicable information is issued; and the installed condition is verified. The table is a teaching record, not a report of actual Kentucky project actions or a site authorization.

Nonconforming Work and Corrective-Action Pathways

Nonconforming work is work that does not satisfy an applicable requirement. The requirement may come from a drawing, specification, approved submittal, standard plan, permit, testing criterion, accepted material list, or authorized change. The phrase is deliberately broader than "defective work." Some nonconforming conditions are obviously unacceptable. Others require engineering evaluation before the project can determine whether the deviation affects performance, safety, durability, maintainability, appearance, payment, or another project requirement.

A sound nonconformance process protects both technical quality and fairness. It prevents informal acceptance of undocumented deviations, but it also prevents automatic removal of work when an engineered disposition may be appropriate. The goal is to establish the requirement, document the actual condition, control immediate risk, route the issue to the person with authority, and verify that the final disposition has been executed and recorded.

4.1 Start with the controlling requirement

The first step is to identify precisely what requirement the work does not meet. "Looks wrong" is not a sufficient technical basis. A nonconformance statement should link the observed condition to a requirement.

Examples:

- installed pipe invert differs from the approved plan elevation;
- pavement density result is below the specified acceptance threshold;
- sign support is installed outside the approved location tolerance;
- concrete placement used material outside the approved mix-design parameters;
- installed signal equipment differs from the approved submittal;
- curb-ramp geometry fails an applicable dimensional criterion;
- drainage structure material is not the specified or approved product; or
- required inspection/test documentation is missing.

Some documentation nonconformances are as important as physical defects. If the contract requires traceable material certifications or testing and they are unavailable, the project may not have evidence that the installed work meets the requirement even if the work appears satisfactory.

4.2 Classify the condition before choosing a disposition

DISPOSITION	EVIDENCE TO RETAIN
Correct / rework	Requirement restored and result verified
Remove / replace	Original condition, replacement identity and acceptance evidence
Repair	Engineered repair basis, execution conditions and verification
Engineering evaluation	Actual condition, analytical basis, limits and authority
Accept deviation	Explicit authorized acceptance and record-document update
Investigate further	Unresolved facts, interim controls and decision owner

Classification helps determine urgency and authority. A useful project-specific classification may distinguish:

Immediate safety or stability concern. Work or surrounding conditions may present an imminent risk to workers, road users, the public, adjacent property, or the stability of the project. The first action is control of the hazard and appropriate escalation, not paperwork completion.

Critical technical nonconformance. The condition may affect structural capacity, hydraulic performance, traffic operation, accessibility, durability, or another significant design function.

Routine quality deficiency. The condition clearly requires correction but does not present an immediate high-consequence technical question.

Documentation or process deficiency. Required records, approvals, tests, or submittals are incomplete or missing.

Potential nonconformance requiring verification. The available information suggests a deviation, but additional measurement, testing, or document review is needed before the condition is confirmed.

The labels may differ by project. The purpose is to prevent the same administrative response from being applied to every issue regardless of consequence.

4.3 Control the work while the issue is unresolved

Once a material nonconformance is identified, the project must prevent the condition from becoming more difficult to correct or from affecting additional work. Controls may include:

- stopping the affected activity within contractual authority;
- preventing cover-up or concealment;
- marking or segregating nonconforming material;
- protecting the area from traffic or loading;
- holding related work that depends on the condition;
- preserving samples or test evidence;
- documenting the condition before repair; or
- implementing an approved temporary protective measure.

The control should be proportional to the issue. A documentation discrepancy may not justify stopping unrelated work. A potentially unstable excavation or structural condition may require immediate restriction.

4.4 Notification should identify what decision is needed

A nonconformance record should be routed promptly to the people who need to know, but broad distribution alone does not produce resolution. The notification should identify:

- requirement;
- observed deviation;
- location/quantity affected;
- immediate controls applied;
- available evidence;
- proposed corrective action if any; and
- decision required and responsible authority.

A field inspector may be able to require removal of obviously unacceptable debris but not approve a structural repair. A contractor may propose a repair but not accept a deviation from design. The EOR may determine technical acceptability but not resolve compensation. The owner may have contractual acceptance authority but rely on engineering evaluation.

4.5 Removal and replacement is the clearest but not always the only pathway

When nonconforming work can be removed and replaced without creating disproportionate risk or collateral damage, replacement may be the simplest disposition. It restores the condition to the approved requirement and minimizes the need for engineering justification.

However, removal itself can create risk. Replacing an embedded anchor may damage surrounding concrete. Removing a drainage structure after adjacent utilities and pavement are complete may disrupt other systems. Reconstructing a curb ramp may affect traffic-control staging. The decision should therefore consider the technical consequences of correction, not merely the fact that replacement is conceptually straightforward.

Removal-and-replacement records should still document the original condition and verify the replacement. Otherwise, the project loses evidence of the issue and cannot identify whether similar work may be affected.

4.6 Repair requires a defined technical basis

A repair restores acceptable function without necessarily returning the work to its original specified condition. Repairs may involve patching, strengthening, regrading, adding material, replacing components, modifying connections, reworking pavement, sealing, adjusting equipment, or other actions.

A repair plan should define:

- defect being addressed;
- extent of affected work;
- preparation/removal required;
- repair materials and procedures;
- dimensional or performance criteria;
- inspection/testing of the repair;
- cure or waiting periods where applicable;
- limitations; and
- final acceptance criteria.

A verbal statement to "patch it" is not a repair plan when the defect affects performance or durability.

4.7 Engineering evaluation can support acceptance or redesign

Some deviations require analysis to determine whether the installed condition can remain. Engineering evaluation may consider structural capacity, hydraulic performance, durability, fatigue, safety factors, accessibility, geometric criteria, clearances, operations, maintenance, or other project-specific requirements.

The evaluation should be based on the actual condition, not an approximate description. If a pipe is out of profile, obtain survey data. If anchor rods are misplaced, measure coordinates and projection. If concrete strength is questionable, assemble test history and placement information. If a utility conflicts with a foundation, verify location and depth.

The resulting disposition may be:

- accept as installed because performance remains satisfactory;
- accept with limitations or monitoring;
- perform a defined repair;
- redesign adjacent work to accommodate the condition;
- remove and replace; or
- obtain additional investigation before a decision.


4.8 Formal acceptance of a deviation should be explicit

If work is accepted despite not meeting the original requirement, the project record should make that decision explicit. The record should identify the deviation, technical basis, authority, any compensation or contractual treatment handled elsewhere, and record-document update.

Silent acceptance creates several problems. Future inspectors may believe the work conforms to the original plan. Maintenance personnel may not know the actual condition. A later failure investigation may find no explanation. Final as-built information may be inaccurate.

Formal acceptance does not mean the original requirement was unnecessary. It means the particular deviation was evaluated and dispositioned through the project's authorized process.

4.9 Failed tests require more than a retest



Preserve the original failed or questioned result, establish validity and retain the complete disposition history.

A common but incomplete response to a failed test is to perform another test until a passing result is obtained. Retesting can be appropriate, but the project should first understand what the test represents and why it failed.

Questions include:

- Was the original test valid?
- What work area or lot does it represent?
- Was sampling performed correctly?
- Could the failure indicate a localized condition or broader process issue?
- Has additional work been placed using the same process/material?
- Does the specification define retest, investigation, removal, pay adjustment, or corrective procedures?
- Could corrective work alter another accepted property?

A passing retest at a different location does not automatically erase a valid failing result unless the acceptance framework allows that interpretation.

4.10 Nonconforming materials should be controlled before incorporation

Materials that do not meet approval, certification, identification, or testing requirements should be controlled so they are not inadvertently installed. This may involve tagging, segregation, quarantine areas, electronic status control, or supplier disposition.

The same principle applies to fabricated components. If a sign structure, signal pole, bearing, precast element, drainage component, or electrical assembly arrives with questionable documentation or visible damage, the project should establish its status before installation.

Once installed, verification and correction become more difficult. Material control is therefore one of the most cost-effective nonconformance controls.

4.11 Deviation from an approved submittal is still a nonconformance

The field sometimes focuses on the contract plan and overlooks the approved construction-specific submittal. If installed work differs from an approved shop drawing, fabrication drawing, product data, or mix design, that difference may require evaluation even if the original contract documents were less detailed.

The reviewer should determine whether the submittal detail was required for function, fabrication, coordination, or merely illustrative. If the deviation changes a connection, component, material, dimension, or interface that was part of the accepted submittal, the project should not assume it is harmless.

4.12 Workmanship deficiencies can become performance deficiencies

Some defects appear cosmetic but may have technical consequences. Poor concrete finishing can affect drainage or ride. Honeycombing can reduce cover and durability. Poorly aligned pavement markings affect traffic operation. Improperly sealed joints allow water intrusion. Damaged coatings accelerate corrosion. Rough or uneven curb-ramp finishes can affect accessibility.

The evaluation should therefore distinguish aesthetic requirements from performance implications rather than dismissing workmanship issues categorically.

4.13 Stop-work concepts should be used with defined authority

Stopping work can be necessary when continued activity would create danger, conceal evidence, expand a defect, or make correction impractical. But stop-work authority is contractual and role-specific. Field personnel should know what they are authorized to stop, who must be notified, and how work is released.

A targeted hold may be more appropriate than stopping an entire project. For example, hold backfill at one drainage structure while allowing unrelated paving elsewhere. The objective is risk control, not punishment.

Release from the hold should be documented when the required condition has been met.

4.14 Corrective action is broader than correction

A correction fixes the specific defect. Corrective action addresses why the defect occurred and reduces recurrence. If a crew repeatedly installs drainage structures at wrong elevations because it uses an outdated staking file, resetting one structure is correction. Updating the survey file distribution and verification process is corrective action.

Repeated issues should therefore trigger a broader review of:

- design/document clarity;
- submittal quality;
- material source;
- equipment calibration;
- survey/layout process;
- work method;
- training;
- supervision;
- inspection timing; or
- communication.

Corrective action should be proportional to the significance and recurrence of the issue.

4.15 Verify repair before closing the issue

A nonconformance is not closed when someone says the repair is complete. Closure requires evidence that the approved disposition was implemented and the final condition meets the defined acceptance criteria.

Closure evidence may include:

- follow-up inspection;
- measurements;
- photographs;
- survey data;
- test results;
- engineer's review;
- material records;
- marked-up plan; and
- completion sign-off by the authorized party.

If the repair itself becomes concealed, verify it before concealment.

4.16 Track the complete issue lifecycle

An effective nonconformance record shows the progression:

Requirement -> observed condition -> immediate control -> technical evaluation -> approved disposition -> implementation -> verification -> closure -> record update.

This lifecycle should remain visible even if several documents are used. A deficiency report may initiate the issue, an RFI may obtain design input, a change order may authorize the work, and an inspection report may verify closure. The documents should reference one another.

4.17 Applied example - asphalt density below criterion

A density result for a paving lot is below the contract criterion. The immediate question is not simply whether to roll the mat more. The team should identify the lot represented, test validity, mat temperature and timing, additional test requirements, whether more material from the same process has been placed, specification disposition provisions, and whether additional rolling could damage the mat.

The final disposition may involve additional testing, pay adjustment, removal and replacement, engineering/agency evaluation, or another specification-defined outcome. The project should document the original failing result and the complete disposition rather than retaining only the later passing information.

4.18 Applied example - drainage pipe installed off alignment

Survey indicates a storm pipe is 1.5 feet left of plan alignment over a 60-foot run. The pipe connects properly at both structures and has acceptable slope, but the shifted alignment reduces clearance to a proposed utility.

The deviation cannot be evaluated solely as a drainage issue. The engineering review must determine actual clearance, utility requirements, future maintenance access, easement/right-of-way constraints, and whether the record plans can accurately reflect the condition. Acceptance may be possible, but only after the multidisciplinary effect is evaluated.

4.19 Applied example - unapproved signal equipment substitution

A contractor installs a component that is functionally similar to the approved signal equipment but has a different manufacturer and model. The unit fits the cabinet and operates during initial testing.

Function during one test is not sufficient evidence of conformance. The project should determine approval/listing status, specified performance, compatibility, warranty, communications protocols,

maintenance requirements, spare-parts implications, and whether owner approval is required. If the substitution is acceptable, it should be formally documented and incorporated into final records.

4.20 Applied example - curb ramp outside tolerance

Field measurements indicate a completed curb ramp exceeds an applicable slope criterion at one location. Grinding or local patching is proposed.

The repair must be evaluated as geometry, not merely surface treatment. Correcting one slope can alter cross slope, landing geometry, detectable-warning position, drainage, or transition to the sidewalk. The final repair should be measured after completion against all affected criteria, not just the originally failing dimension.

4.21 Applied example - missing test documentation at closeout

A project reaches closeout and the team cannot locate required test documentation for a completed drainage material. The work has been buried for months and appears to be functioning.

The absence of evidence is a process nonconformance. The project should reconstruct available material certifications, delivery records, approved product information, inspection reports, photographs, and supplier documentation. The authorized party must determine whether the reconstructed evidence is sufficient or whether additional investigation is required. Simply marking the checklist complete because the physical work is inaccessible undermines the audit trail.

4.22 Module takeaway

Nonconforming work should be managed through a controlled lifecycle rather than through informal field negotiation. Identify the requirement, document the actual condition, classify significance, control immediate risk, route the issue to the proper authority, select a technically justified disposition, verify implementation, and preserve the decision in the project record.

The process is effective when it is proportional. Routine defects should not require unnecessary bureaucracy, and significant deviations should not be reduced to a casual field note. The level of review should match the consequence, uncertainty, and professional judgment involved.

4.23 Module practical checklist

- Link every nonconformance to an identifiable requirement.
- Classify urgency and consequence before selecting the response.
- Prevent concealment or propagation of unresolved significant defects.
- Document the original condition before repair when practical.
- Route decisions to people with actual technical and contractual authority.
- Use removal/replacement, repair, engineering evaluation, redesign, or formal acceptance as distinct disposition pathways.
- Treat failed tests under the specified acceptance framework; do not simply test until a pass appears.
- Control questionable materials before installation.
- Evaluate deviations from approved submittals, not only from contract drawings.
- Distinguish correction from corrective action when defects recur.
- Verify the approved disposition before closure.
- Link the entire issue lifecycle and update final record information.

MODULE 5 | 40 MINUTES

Testing, Quality Records, Change Documentation & Project Closeout

Project closeout is not the moment when quality documentation suddenly becomes important. A defensible closeout file is the accumulated product of decisions made throughout construction. Testing

records, inspection reports, submittals, RFIs, deficiency logs, approved changes, photographs, surveys, material certifications, and as-built information must be traceable enough to show that significant requirements were verified and significant deviations were resolved.

The quality record has two audiences. The first is the construction team that needs information to make timely acceptance and corrective decisions. The second is the future owner, maintainer, auditor, engineer, or investigator who may need to understand what was actually installed and why a particular deviation was accepted. The record should support both.

5.1 Testing is part of the acceptance system

Testing should be understood as a planned element of acceptance rather than as a collection of laboratory reports. Specifications may define which properties are tested, sampling frequencies, lot boundaries, qualification requirements, acceptance thresholds, retesting, pay adjustments, and corrective procedures.

The project team should know before the activity begins:

- what tests are required;
- who performs them;
- how locations or samples are selected;
- what work each result represents;
- when results must be available;
- what constitutes failure;
- who receives the result; and
- what happens if the criterion is not met.

This is especially important when work will be covered or when subsequent operations depend on acceptance of the previous layer.

5.2 Material certifications are not substitutes for field verification

Certificates, approved product lists, mill reports, mix designs, supplier data, and manufacturer certifications establish important information about materials. They do not necessarily establish that the correct material was delivered to the correct location, stored properly, installed correctly, or protected from damage.

A complete quality system links material approval with field identity. The record should answer:

- What product or material was approved?
- What was delivered?
- Can the delivered item be traced to the approval/certification?
- Where was it installed?
- Was installation inspected or tested as required?
- Were substitutions or damaged materials documented?

Traceability is especially important for fabricated structural items, electrical/traffic equipment, concrete and asphalt materials, drainage products, reinforcing steel, coatings, and proprietary systems.

5.3 Questionable test results deserve technical review

A questionable result may arise from sampling error, equipment malfunction, poor specimen handling, transcription, unusual material variability, or actual deficient work. The project should avoid two extremes: accepting every result without question or dismissing an inconvenient failure without evidence.

When validity is questioned, document why. Review calibration, sample identification, chain of custody, test method, technician qualification, environmental conditions, calculations, and represented work. If a test is invalidated, the basis should be recorded. If it remains valid, follow the specified disposition process.

5.4 Reconcile test data with field conditions

Test data should not be interpreted in isolation from the work. Suppose compaction tests pass but the inspector observes rutting or pumping. Passing point tests may not explain the broader condition. Conversely, a localized failing test may occur in an area that was subsequently reworked and retested.

A quality review should integrate:

- test location;
- represented lot;
- construction sequence;
- weather or material conditions;
- observed workmanship;
- repairs/rework;
- retests; and
- final accepted condition.

The objective is not to override test criteria with visual judgment. It is to understand whether the combined evidence tells a coherent story.

5.5 Deficiency logs provide management visibility

A deficiency log is useful when it captures open issues at a level that management can act upon. It should not replace the detailed nonconformance record; it should summarize status.

Useful fields include:

- issue number;
- date identified;
- location/work item;
- brief description;
- significance/category;
- responsible party;
- required disposition;
- due date;
- current status;
- related RFI/NCR/change document; and
- closure date.

Aging open issues should be reviewed. A minor unresolved item can become a closeout obstacle if it remains undocumented for months.

5.6 Punch lists are not substitutes for construction quality control

Punch lists are valuable near completion, but they should capture remaining visible work rather than become the primary mechanism for finding defects. Many important transportation quality characteristics are concealed long before punch-list stage.

A mature project closes issues continuously. Underground defects are resolved before backfill. Pavement-layer deficiencies are addressed before the next lift. Embedded items are checked before concrete. Traffic equipment is tested before final operation. The final punch list should therefore be relatively focused on remaining completion items rather than reconstructing months of unresolved quality problems.

5.7 Change documentation should tell the technical story

A change record is strongest when it explains not only what changed but why. A later reviewer should be able to determine:

- original requirement;
- condition or reason for change;
- technical evaluation;

- affected disciplines;
- final approved configuration;
- cost/schedule treatment if documented elsewhere;
- implementation evidence; and
- record-plan update.

This level of traceability prevents final plans from becoming a collection of unexplained redlines.

5.8 Field sketches and redlines require control

Field sketches, marked-up plans, and redlines are useful during construction, but uncontrolled copies can become sources of error. A field sketch should identify author, date, affected sheets, purpose, approval status, and relationship to any formal change document.

Redlines should be updated consistently so the project does not maintain conflicting records. If a field change is later superseded, the record should show the final condition rather than preserving an obsolete intermediate mark as if it were final.

5.9 Record information must distinguish design from observed construction

"As-built" terminology varies by owner and contract. Some record drawings represent contractor-reported changes; others include survey-verified information; others are engineer-prepared record documents based on information furnished by others. The record should not imply a level of field verification that was not performed.

A professional engineer preparing record information should understand the source and limitations of the data. If elevations are based on contractor redlines rather than independent survey, the record should be managed according to the project's requirements and professional obligations.

5.10 Closeout requires resolution of open technical issues



Closeout is a technical reconciliation process, not merely a document-transmittal event. Contextual illustration, not a documented project record.

Substantial or final completion should not conceal unresolved technical questions. The project should review open RFIs, nonconformance reports, failed tests, deficiency items, substitutions, temporary repairs, and change requests.

A closeout review should ask:

- Are any technical issues still awaiting disposition?
- Were all approved repairs verified?
- Were failed tests resolved under the applicable acceptance framework?
- Are accepted deviations reflected in final records?
- Were temporary conditions removed or converted to approved permanent conditions?
- Are required certifications and warranties available?

- Are operations/maintenance documents consistent with installed equipment?

5.11 Missing records are themselves a project risk

A missing record does not always mean the physical work is defective, but it creates uncertainty. The response should be proportional to the significance of the missing evidence.

Possible reconstruction sources include:

- daily reports;
- delivery tickets;
- photographs;
- survey data;
- supplier records;
- laboratory databases;
- contractor quality records;
- emails/RFIs;
- material certifications; and
- later verification testing where technically appropriate.

The authorized party must decide whether reconstructed evidence is sufficient. The process should not create a false record.

5.12 Record retention supports future maintenance and accountability

Transportation infrastructure may remain in service for decades. Future maintenance engineers may need to know actual utility locations, accepted deviations, repair materials, equipment models, structural modifications, drainage changes, or unresolved limitations.

A quality file therefore has operational value beyond contract administration. Good closeout records reduce future investigation costs and help avoid damaging concealed systems during maintenance.

5.13 Auditable files use cross-references

RECORD LINK	TRACEABLE CONNECTION
Requirement → field evidence	Current sheet / specification and exact location
Field evidence → evaluation	Measurements, tests, photographs and technical issue
Evaluation → disposition	Technical basis and authorized decision-maker
Disposition → implementation	Issued revision and field distribution
Implementation → closure	Verification, final records and retained history

An auditable file should allow a reviewer to move from one issue to the supporting evidence without searching unrelated folders. Issue identifiers, hyperlinks in document-management systems, consistent file names, station/location tags, and related-document fields can create this linkage.

For a nonconforming drainage structure, for example, the issue record may reference:

- inspection report;
- survey points;
- photographs;
- RFI;
- EOR disposition;

- repair detail;
- follow-up inspection;
- final survey; and
- record-plan revision.

The complete chain demonstrates closure.

5.14 Quality dashboards should not hide technical detail

Dashboards are useful for summarizing open issues, test status, and completion progress. They should not become the only record. A green status indicator is meaningful only if the underlying evidence is preserved.

Management metrics can include:

- number of open deficiencies by age;
- repeated issue types;
- testing completion rate;
- failed-test closure time;
- outstanding submittals/RFIs;
- unresolved changes; and
- closeout-document completeness.

Metrics should drive attention toward risk, not encourage premature closure merely to improve the dashboard.

5.15 Applied example - concrete test history

A series of concrete placements includes one strength result below the specified criterion. Later cores or additional evaluation may support acceptance, depending on the contract and engineering requirements. The project record should preserve the original result, placement location, batch information, sampling details, later investigation, engineering disposition, and any repair or acceptance decision.

Deleting or ignoring the original failure because a later result is favorable destroys traceability.

5.16 Applied example - utility relocation not reflected in records

A utility was relocated during construction to resolve a drainage conflict. The work was approved by the utility owner and design team, but the final plan markup still shows the original location.

This is a closeout defect because future maintenance may rely on the record. The project should update the record information with the accepted location and identify the source of the final coordinates/elevations.

5.17 Applied example - repeated pavement deficiency

Several pavement lots show similar surface irregularities even though acceptance testing is mostly passing. The quality record should allow the team to compare dates, equipment, plant production, weather, crew, rolling pattern, and testing. The pattern may indicate a construction-process issue that deserves corrective action even if individual lots are contractually acceptable.

5.18 Applied example - incomplete equipment documentation

A traffic-control cabinet and communications equipment have been installed and tested, but serial numbers, final configuration files, and warranty documentation are incomplete. Physical completion does not equal documentation completion. The owner may need those records for maintenance, cybersecurity/configuration control, spares, and warranty claims.

Closeout should therefore include both operational testing and information turnover.

5.19 Module takeaway

Testing, quality records, change history, and closeout documentation form one continuous evidence system. Testing must be interpreted within its sampling and acceptance framework. Deficiencies should be tracked to closure. Changes should tell a complete technical story. Record information should accurately represent its source and level of verification. Missing records should be treated as uncertainty requiring a deliberate response.

A successful closeout allows a future qualified person to determine what was required, what was installed, what changed, what was tested, what deviations were accepted, and where the evidence is stored.

5.20 Module practical checklist

- Define testing and acceptance requirements before work begins.
- Link material approval to delivered and installed material identity.
- Investigate questionable test validity rather than ignoring inconvenient results.
- Interpret testing together with location and construction history.
- Maintain an actionable deficiency log and review aging issues.
- Close quality issues throughout construction rather than deferring them to punch list.
- Document why changes occurred and how they were approved.
- Control field sketches and redlines as revision-sensitive information.
- Distinguish record information based on survey/verification from information furnished by others.
- Reconcile open RFIs, failed tests, nonconformances, substitutions, and temporary repairs before closeout.
- Reconstruct missing evidence transparently; do not create false certainty.
- Preserve records useful to future maintenance and operations.
- Use cross-references so issue histories can be audited efficiently.

MODULE 6 | 35 MINUTES

Applied Transportation Project Scenarios & Professional Judgment

Professional judgment is most visible when the documents and the field do not align cleanly. The engineer must identify what is known, what remains uncertain, what requirement controls, which disciplines are affected, who has authority to decide, and what evidence is needed before the work can proceed or be accepted. This module applies that reasoning to transportation scenarios.

The scenarios are not intended to prescribe one contractual answer. Project delivery methods and owner procedures vary. The objective is to practice a repeatable decision framework:

Requirement -> Field evidence -> Consequence -> Authority -> Options -> Approved disposition -> Verification -> Record update.

6.1 Scenario - drainage conflict discovered during excavation

A contractor excavating for Structure S-45 uncovers an existing fiber-optic duct bank 18 inches from the planned structure wall. The record utility plans show the duct bank farther away. The contractor proposes shifting the structure 4 feet downstream and rotating the inlet top to avoid the conflict.

The first task is to document the actual utility location, structure geometry, pipe inverts, gutter low point, adjacent utilities, and proposed shift. The drainage engineer should evaluate whether the move affects pipe slope, inlet capture, spread, connection geometry, maintenance access, and downstream structure depth. Roadway and utility disciplines may also need review.

The field should not treat the move as a simple construction adjustment until the system effects are understood. If the change alters approved geometry materially, it should enter the controlled design/change process and final record information should reflect the installed location.

6.2 Scenario - roadway elevation conflicts with driveway tie-in

During fine grading, survey indicates the constructed roadway profile is consistent with the approved plans, but an existing commercial driveway is substantially lower than shown in the survey base. The planned tie-in would create an impractical driveway grade and drainage problem.

The field condition differs from the design assumption. The appropriate response is to verify existing grades, document the limits of the discrepancy, and assess the effects of alternative tie-ins. Roadway profile, sidewalk/accessibility, drainage, right-of-way, and property impacts may all be involved.

A local grading adjustment may be possible, but the decision should be made using coordinated geometry rather than by field smoothing alone.

6.3 Scenario - shop drawing matches installation but not plan

A sign structure has been fabricated and erected according to an approved shop drawing. During final inspection, the engineer discovers that the shop drawing used a support spacing different from the contract plan. The difference was not identified as a deviation during submittal review.

The project must determine whether the installed condition is technically acceptable, whether the shop drawing approval constituted authorized acceptance of the deviation under the contract, and whether another discipline or design assumption is affected.

The answer is not automatically "approved shop drawing controls" or "plan controls." The project needs a documented technical and contractual disposition, and final records should show the actual accepted configuration.

6.4 Scenario - failed compaction test after next layer placed

A density test result is received late and indicates failure in a roadway embankment area that has already been covered by the next lift. The contractor requests a retest from the surface.

The team should establish the represented lot, validity of the original test, location and depth, subsequent work placed, and specification provisions. A surface retest may not represent the failed layer. Investigation options may include additional testing, excavation, engineering evaluation, or another specified procedure.

Late results expose a process issue as well as a technical issue. The project should evaluate whether testing/reporting timing needs corrective action to prevent recurrence.

6.5 Scenario - pavement-marking layout conflicts with final geometry

Permanent marking plans show lane lines based on the original curb-return geometry. A field-approved roadway revision changed the curb return, but the marking plan was not updated. The marking subcontractor lays out the original geometry and notices that the taper no longer aligns with the actual lane edge.

This is a document-integration issue. The team should stop before permanent material is placed, verify the approved roadway revision, route the marking geometry to the traffic discipline, and issue coordinated direction. The final marking record should reflect the accepted layout.

The case illustrates why discipline-specific plans must be updated when an upstream geometric change affects them.

6.6 Scenario - signal pole conflicts with accessible route

A signal pole location satisfies the signal plan but, after sidewalk formwork is set, it becomes clear that the foundation/pole and pedestrian pushbutton arrangement will constrain the clear pedestrian route.

Resolution requires signal, roadway/accessibility, and possibly utility coordination. Moving the pole can change mast-arm reach, underground conduit, pushbutton geometry, clear zone, and visibility. Adjusting sidewalk geometry may create slope or landing issues.

The team should use measured field geometry and the governing accessibility/traffic requirements, not simply choose the easiest construction option.

6.7 Scenario - recurring drainage structure elevation errors

Three drainage structures in the same crew's work are found outside the expected elevation range. The first two were individually adjusted. The third indicates the issue may be systemic.

The project should pause and investigate the common process: staking file, benchmark, survey setup, plan revision, crew interpretation, structure fabrication, or measurement method. Correcting each structure without addressing the recurring cause risks additional nonconformance.

This is the point where quality management and engineering coordination meet. The immediate defects require correction; the process requires corrective action.

6.8 Scenario - proposed product substitution affects maintenance

A contractor proposes an alternative traffic-control device that meets nominal performance requirements and can be delivered sooner. The substitute has different mounting hardware, communications configuration, and replacement parts.

The review should address more than initial function. Owner maintenance staff may need to evaluate compatibility, spares, configuration, warranty, and lifecycle implications. Structural/electrical interfaces may also differ.

A technically acceptable substitute should be formally approved and integrated into final equipment records.

6.9 Scenario - installed work differs from approved material

An inspector discovers that several drainage structures were cast with a component from a different manufacturer than the approved submittal. The components appear dimensionally compatible.

The project should verify material properties, product approval status, structural/performance requirements, compatibility, and extent of installation. If equivalent, an authorized substitution or acceptance pathway may exist. If not, repair or replacement may be required.

The case illustrates why traceable delivery records and material identification matter before installation.

6.10 Scenario - contractor proposes repair to nonconforming concrete

A concrete element has localized honeycombing. The contractor proposes removing loose material and placing a proprietary repair mortar.

Before acceptance, the responsible engineer should determine the extent and significance of the defect, whether reinforcement or cover is affected, whether the proposed material is compatible, surface preparation, curing, inspection/testing, and final acceptance criteria.

A generic repair product does not by itself establish that the repair restores the required durability or function.

6.11 Scenario - field direction given verbally

A superintendent states that an owner representative verbally approved moving a conduit around a conflict. No written record exists, and the conduit is now covered.

The project should reconstruct the decision using participants, photographs, measurements, plan information, and any contemporaneous communication. The responsible discipline should determine whether the installed route is acceptable and whether record documents must be updated.

The lesson is not that verbal communication is prohibited. It is that technically significant decisions must be captured before memory becomes the only evidence.

6.12 Scenario - questionable test result

A laboratory result is far outside the expected range, but other results from the same material are normal. The contractor argues the result is obviously wrong.

The project should investigate test validity systematically: sample identity, chain of custody, equipment calibration, technician notes, calculation, specimen condition, and test method. If the result is invalidated, document the basis. If not, treat it as valid evidence and follow the acceptance process.

Professional judgment means evaluating evidence, not selecting the result that is most convenient.

6.13 Scenario - temporary repair remains at closeout

During construction, a damaged conduit was temporarily rerouted above grade to maintain system operation. At closeout, the temporary condition is still in place because the permanent repair was never tracked.

Closeout review should identify temporary conditions explicitly and require final disposition. If the temporary arrangement is to become permanent, it must be evaluated and documented as such; otherwise it should be removed and the approved permanent system restored.

6.14 Scenario - unresolved utility record discrepancy

Utility as-built information from the contractor differs from final survey points collected by the owner. The discrepancy is several feet near a future maintenance access area.

The project should reconcile the sources before final record issuance. If uncertainty remains, the record should represent that uncertainty accurately rather than choosing one dataset without explanation.

6.15 Scenario - repeated RFI indicates design-document weakness

Multiple RFIs ask essentially the same question about a drainage detail used at many locations. Each response resolves one structure, but construction continues to generate new RFIs.

The issue may be better addressed through a global clarification or plan revision than through repetitive individual responses. A recurring question is a signal that the document system may need correction.

6.16 A professional judgment matrix

CONSEQUENCE / UNCERTAINTY	LOW	MODERATE	HIGH
Low	Routine control	Verify next step	Clarify / obtain evidence
Moderate	Targeted technical assessment	Engineering evaluation	Hold affected work / escalate
High	Engineering decision	Hold / multidisciplinary input	Immediate control / senior technical authority

Conceptual judgment aid. Project requirements and actual authority govern; reversibility and concealment affect urgency.

When a transportation issue is unclear, classify it across five dimensions.

Requirement certainty: Is the governing requirement clear, ambiguous, or conflicting?

Field certainty: Is the actual condition measured and documented, or still uncertain?

Consequence: Could the issue affect safety, capacity, drainage, operation, accessibility, durability, maintainability, or only minor appearance?

Authority: Who is authorized and qualified to make the needed decision?

Reversibility: Can the work be corrected easily now, or will continued work make correction expensive or impossible?

The matrix helps determine urgency. Low-certainty, high-consequence, low-reversibility conditions deserve early escalation and controlled hold points.

6.17 Communication principles for defensible resolution

A defensible technical resolution is concise about what was evaluated. It should identify the condition, documents reviewed, assumptions, analysis or basis, disposition, implementation requirements, verification, and any limitations.

Avoid broad language that suggests more review than actually occurred. If only drainage performance was evaluated, do not state that the entire field change is "approved" unless the reviewer has authority and basis to approve all affected aspects.

6.18 When to involve another discipline

Escalate across disciplines when the proposed action changes another system's geometry, load, access, performance, sequence, or regulatory criterion. Examples include:

- drainage relocation affecting roadway grades;
- signal foundation move affecting pedestrian accessibility;
- utility relocation affecting structural foundation or drainage;
- sign relocation affecting sight distance;
- roadway profile change affecting bridge approach or drainage;
- substitution affecting electrical load or structural anchorage.

Multidisciplinary review is not bureaucracy when the systems genuinely interact.

6.19 When to stop and obtain more evidence

Professional judgment includes recognizing when there is not enough information to decide. More evidence may be needed when:

- field dimensions are approximate;
- test validity is disputed;
- concealed conditions are unknown;
- the governing document revision is unclear;
- the proposed repair depends on actual defect extent;
- utility location is unverified; or
- another discipline's effect has not been evaluated.

A short delay to obtain decisive information can prevent a much larger corrective effort.

6.20 Closing the loop

Every significant scenario should end with a closed evidence chain. The final record should show:

- issue identified;
- requirement and actual condition;
- technical/contractual decision;
- approved implementation;
- verification; and
- final document update.

Open loops create future uncertainty. Closed loops convert project experience into a defensible record.

6.21 Course synthesis - the eight-question field test

Before a technically significant transportation field decision is implemented, ask:

1. What is the controlling requirement? 2. Is the field condition measured and documented accurately? 3. Which disciplines or systems are affected? 4. What is the consequence if the assumption is wrong? 5. Who has authority and competence to decide? 6. Is the proposed action a clarification, correction, repair, substitution, or design change? 7. What evidence will verify successful implementation? 8. How will the final condition be reflected in the project record?

If those questions are answered clearly, most construction-phase coordination problems become manageable.

6.22 Module takeaway

The highest-value engineering behavior during construction is disciplined classification. Engineers do not need to personally solve every field problem. They need to identify the controlling requirement, the actual condition, the affected interfaces, the decision authority, and the evidence needed for closure.

Transportation projects are particularly dependent on this discipline because many systems share the same corridor. A small change can propagate across drainage, roadway, utilities, traffic, accessibility, structures, and maintenance. The professional record should show that these effects were considered deliberately rather than discovered after the work was complete.

6.23 Module practical checklist

- Use the requirement-field evidence-consequence-authority-options-disposition-verification-record framework.
- Verify field measurements before making geometry-sensitive decisions.
- Escalate changes that affect another discipline.
- Treat late failed tests as both technical and process issues.
- Update dependent discipline documents after upstream changes.
- Investigate recurring deficiencies for systemic causes.
- Evaluate substitutions for interface and lifecycle effects, not only nominal function.
- Preserve the original condition and evidence before repair when practical.
- Reconstruct significant verbal decisions and formalize the final disposition.
- Document the basis for invalidating questionable test results.
- Track temporary conditions through final removal or formal acceptance.
- Reconcile conflicting record information before closeout.
- Use global clarification when repeated RFIs reveal a common document weakness.
- Stop and obtain more evidence when uncertainty is material to consequence.
- Close the technical loop in the project record.

Principal references

Use the project-adopted source editions and contract requirements. The following source families support the coordination, evidence, acceptance and record-control principles taught here.

- Florida Department of Transportation, 2026 FDOT Design Manual, including plans-development and plans-production provisions.
- Florida Department of Transportation, FY 2026-27 Standard Specifications for Road and Bridge Construction and the Standard Specification Library.
- Florida Department of Transportation, FY 2026-27 Standard Plans for Road and Bridge Construction.
- Florida Department of Transportation, applicable Traffic Engineering Manual, construction administration, testing, and project documentation guidance.
- Federal Highway Administration transportation design, construction quality assurance, contract administration, inspection, and project-delivery resources.

- U.S. Army Corps of Engineers, Construction Quality Management for Contractors (CQM-C) quality-control framework.
- Construction Specifications Institute construction-document, submittal, RFI, change, and closeout practice concepts.
- National Society of Professional Engineers, Code of Ethics for Engineers, particularly public welfare, competence, truthful professional communication, and responsibility for professional work.
- Project-specific transportation plans, specifications, standard plans, approved submittals, RFIs, change documents, testing and inspection requirements, permits, and owner criteria.

Source links

- FDOT Standard Specifications for Road and Bridge Construction. FY 2026–27 applies to the relevant letting period; the project contract determines the controlling edition. Open source
- FDOT Design Manual. Plans development, coordination and production framework; use project-adopted edition. Open source
- FDOT Standard Plans. Confirm applicable edition, index and project modifications. Open source
- FDOT Construction Project Administration Manual. Plans assessment, project documentation, utility work, verification/testing, as-built process and acceptance. Open source
- 23 CFR Part 637, Subpart B. Federal-aid NHS construction quality-assurance framework; application depends on project and program. Open source
- FHWA SHRP2, Managing Utility Conflicts in Kentucky, pp. 1–3. Historical system implementation case; photographs and KURTS screenshot reproduced with source credits. Open source
- Kentucky Highway Knowledge Portal, Tracking Utility Conflicts. Utility conflict data and resolution tracking; Kentucky practice is an instructional comparison, not a Florida requirement. Open source
- USACE ER 1180-1-6, Construction Quality Management. Project quality-management framework; applicable obligations depend on the contract. Open source
- NSPE Code of Ethics for Engineers. Competence, public welfare and truthful professional statements. Open source

Source records checked November 15, 2026. This course explains engineering decisions and does not replace the applicable contract, adopted standards or project-specific technical authority.

Instructor

James Barber, P.E. — Florida Professional Engineer No. 75518. BuilderCE instructor for this civil transportation engineering course.

> **Study guide complete.** Return to the BuilderCE lesson page and select Continue to begin the final examination. A score of at least 70% is required to pass. Retakes are permitted.